Questions & Answers

RFQ/YEMSA/SUP/2022/36 FOR For the Supply, Installation, Commissioning, Operation, Testing and Maintenance of Micro-Grid ESS Solar System Project at Sana'a governorate – Yemen

All below questions received in the pre-bid meeting conducted on Monday 05/12/2022 in pre-bid conference & site visit in the Immigration, Passports and Naturalization Authority (IPNA) building, Yemen – Sana'a (Khawlan Street)

Question 1	Could you please provide us the Drawings and diagrams
UNHCR Answer	Please find them in the attachement, and the same document has been uploaded to UNGM and UNHCR portal

Question 2	Please provide us the Controller specs
UNHCR Answer	It's already specify in BoQ item No. 2 as following description PV Controller - MPPT Voltage Range Input Range 250V~850V - PV Input Capacity ≥ 120KW STC

Question 3	Please provide us the Internal electrical wiring network
UNHCR Answer	The supplier will be scoping to deal with the Output main cable from ATS2 as shown in SLD Drawing and remarks

Question 4	There are no details of the work of the main distribution board, as it became clear during the site visit that the work of the board must be reworked again, and there is no indication in the bill of quantities tables (BOQs).
UNHCR Answer	It is out of the supplier scope of work!

Question 5	Provide us more clarification about the priorities of the operation mode
UNHCR Answer	The operation Priorities it's logical in all solar DC/AC conversion and the important operation for this project is SBU (Solar Battery Utility) The Manufacture of Microgrid ESS will advice you more priorities than the above

Question 6	Point 13 and 14, more clarification about the metal/steel structure.
UNHCR Answer	Item No. 13 Minimum shedding material and foundation requirements room for ESS as

	the containized microgrid ESS built with IP54 enclosures and internal HVAC Item No 14 they are two type as following: Roof type PV mounting Structure Grounding PV Mounting Structure All them must be constructed with IPE120 and HSS100*50*1.3mm Please

Question 7	More clarification of Point 5.1, 20m cable length is not enough
UNHCR Answer	Please stick with BoQ and the variation of increasing or decrease will be decided due the installation stage

Question 8	When submitting the tender documents in the E-tender box, it does not fit for all documents, could you please provide us the maximum folders size – and is it possible for UNHCR to increase the e-tender box capacity
UNHCR Answer	The maximum size limit per file is 10MBs and there is no limitation for the number of files and/or uploads. Suppliers may upload each file one by one or may compress them into a zip file with the maximum size limit of 10MBs. Also, suppliers may always consult with the Supplier User Manual (also available online in the application) for these information and instructions.

Question 9	You have mentioned in the RFQ document the preferable delivery term is 3 months, and in the SoW is five months, what is the Accepted delivery period
UNHCR Answer	It is open for competition

Question 10	Is it possible to extend the tender submission deadline?
UNHCR Answer	After consultatoin with UNHCR managment, it has been approved to extend the tender submission deadline up to **Sunday 25/12/2022 at 23:59 PM (Yemen time)**

Question 11	Is there an option of getting UNHCR support to get the items cleared from custom port and tax authorities
UNHCR Answer	The delivery term requested in the tender is DDP with installatoin, so the bidder to responsible for any payment to government to ensure the delivery DDP with installation to IPNA building

Question 12	Is there any need for Vendor Registration Form
UNHCR Answer	It is not part of the elegibity critira, but at anyway it is requested to complete the supplier registration in UNHCR system in case of new suppliers

Question 13	Could you please provide us all tender annexes, as we cannot download them from UNGM and UNHCR portal
UNHCR Answer	Pleaes find attached all tender annexes, however, all documents are downloadable from UNGM and UNHCR portal

End..