

## QUESTION AND ANSWER (2022/SOQ/RFP/002)

S. #	LOT # & NAME	Query	Reply
1	<b>GENERAL FOR ALL LOTS</b>	What's the budget and schedule of the project?	We don't provide this kind of information
2	<b>GENERAL FOR ALL LOTS</b>	Is Income tax applicable for the mentioned project?	Yes, income tax applicable Supplier is responsible for Income tax, UNHCR will not deduct any amount.
3	<b>GENERAL FOR ALL LOTS</b>	Any tax applicable from provincial Institution?	Supplier is responsible for Income tax, UNHCR will not deduct any amount.
4	<b>GENERAL FOR ALL LOTS</b>	Will the UN provide a tax exemption Certificate if the above taxes are applicable?	If needed, UNHCR will provide tax exemption
5	<b>GENERAL FOR ALL LOTS</b>	Will Escalation in the market prices be adjusted at any stage of the project?	No, there is no provision to change the prices
6	<b>GENERAL FOR ALL LOTS</b>	Would bidders be able to survey the site before bidding?	Yes bidders can visit the site during working days from 9:00 am-2:00pm & 3:00pm -5:00pm at BUITEMS Takatu, Campus, and Focal person for visits is Muhammad Hanif, A.D P&D, BUITEMS.
7	<b>LOT # 2: FUTSAL GROUND</b>	-Mesh Size of Net for Futsal -Height and mesh size of Futsal Court Fencing Wall	-Mesh Size is 4"x4" -Mesh height of Futsal fencing wall is 20 feet and flood light height is 25 feet.
8	<b>LOT#1: PAVILION SHADE:</b>	Column Size not mentioned. Base plate size & Bolts not mentioned. Sheet details are not mentioned either to use corrugated Sheet or plain Sheet. Purlin details are not mentioned in the drawing. Steel Frame details are not mentioned in the drawing. Please re-share the drawings having desired details.	For Football pavilion the contractor has to get it designed, supplied and built from the vender M/S Izhar Steel Pvt or equivalent, and has to quote the rates in sft (inclusive of Designing, fabrication, supplying and erection, paint job etc..)
9	<b>LOT#1: PAVALIN SHADE AT BUITEMS:-</b>	Supplying and installation of pre-Engineer Building (PEB) Roofing system in which include following components in <b>civil works excavation, concreting, pedestals, .....</b> etc. as per our understanding and sectional drawing this shed will be constructed on existing pavilion structure so there will be no civil work exception on steel structure ( Please clarify )	Yes, shade will be built on existing structure, however, there needs to be erected columns, braces etc. for shade supporting thus, it will have required civil work as well for installing the prefabricated steel shade.
10	<b>LOT#1: PAVALIN SHADE AT BUITEMS:-</b>	Fixing Stainless steel net 6-8 MM steel netting or Galvanized netting?	The Net may be read as Galvanizes netting size 4"x4" square, 6mm-8mm.
11	<b>LOT#2: JOGGING TRACK</b>	Material (such P.U. /P.E. or any other one) and thickness of synthetic finish are not mentioned in the drawing nor in BOQ. The thickness of Asphaltic pavement is not mentioned nor in drawing neither in BOQ	Asphalt pavement to be laid and after that track will be built with Synthetic rubber or polyurethane is installed on the top of an asphalt or concrete base. The thickness of synthetic finish may be read as 14mm.

**QUESTION AND ANSWER (2022/SOQ/RFP/002)**

		The outlet from the curb Block is indicated in the drawing but the proper drain/channel is not indicated	The Asphaltic pavement will serve purpose of adhesive cane be replaced with any other suitable adhesive for outdoor purpose  The jogging track is surrounded by flowerbeds the drained water will be disposed in these flowerbeds.
12	<b>LOT # 2: FUTSAL GROUND</b>	It is observed that your indicative brand/[product description is not clearly indicating the product description?	We can't mention a brand, but a high-quality Turf used government approved projects using approved chemicals is recommended
13	<b>LOT#1: PAVALIN SHADE AT BUIITEMS:-</b>	Please clarify question No: 1 lot No: 1 what is the length of pavilion Shade, Detail of frame of shade also share us.	There are three shades Two of the are of 55'x65' and third one is 50'x50'.For further clarification the contractors can visit the site during office hours. For details please refer reply at S.# 08.
14	<b>LOT # 2: FUTSAL GROUND</b>	1. Ref: <u>BOQ of LOT 2 items no 14 Futsal Court fencing wall</u> height of 3 inch & 2 inch pipes is not mentioned and item is missing in the drawing. 2. Ref: <u>BOQ of LOT 2 items no 19 G.I Pipes</u> height of 3-inch pipes is not mentioned and item is missing in the drawing. 3. Please re-share the drawings having desired details.	Height of fence is 20'-0".
15	<b>LOT # 2: FUTSAL GROUND</b>	Item number 11 is not clear (G.I pole) as it is a combination of 17 & 19 whereas it is indicated as an independent item. · Specification of item number 12, net for futsal is also not clear as it is not containing the intermediate distance of steel bars having a diameter of 6-8 mm.	The required G.I Mesh size is 4"x4".
16	<b>LOT#1: PAVALIN SHADE AT BUIITEMS:-</b>	Detail of shade nor BOQ neither Drawing is available	Refer to reply at S #08.
17	<b>LOT#2: JOGGING TRACK BOQ ITEM NO 7 :- ASPHALTIC AND SYNTHETIC TRACK</b>	Supplying and installation of Asphaltic pavement and Synthetic Track works Please provide the clear section of the track or advise us the material to be used in the track surface because asphalt pavement and synthetic are two different prospective ( Please clarify ).	Refer to reply at S #11.