

ANNEX-C (FINANCIAL OFFER FORM / BOQ)
RFP#PAKIS/RFP/22/032

ITEM No.	DESCRIPTION	UNIT	QTY	UNIT RATE (Rs.)	TOTAL AMOUNT (Rs.)
(a)	(b)	(c)	(d)	(e)	(f)
A.	CIVIL WORKS :				
	Ref. Spec. No. 1100, 2100, 2200, 2300, 3000, 6700				
1	Dismantling of kerb stone and stacking/disposal at designated places as per instructions of the Engineer complete in all respects.	Rft	195		
2	Clearing and Grubbing by mechanical means	Sft	7,335		
3	Excavation in foundation of building, bridges etc complete : in ordinary soil.	Cft	845		
4	Filling watering and ramming earth under floor with surplus earth from foundation etc.	Cft	370		
5	Roadway Excavation in Surplus / Unsuitable Common Material	Cft	12,905		
6	RCC in raft foundation slab, base slab of column & ret. wall etc, (1:2:4)	Cft	300		
7	Supply & fabricate M.S. reinforcement for cement concrete (Hot rolled deformed bars Grade 40)	Kg	815		
8	Bitumen coating to plastered / cement concrete surface : 20 lbs. per 100 sft.	Sft	1,340		
9	Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:3:6)	Cft	4,175		
10	Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:4:8)	Cft	205		
11	Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:2:4)	Cft	4,500		
12	Dry rammed shingle brick ballast or stone ballast 1.5" to 2" guage	Cft	6,455		
13	Providing and fixing kerb stone (12"x18"x6") in cement sand mortar 1:3 in center media or round about as specified.	Rft	255		
14	Paint on Concrete work (Kerb stone,Barrier)	Sft	260		
15	Pavement Marking in reflective TP Paint for lines of 6" Inch width	Rft	550		
16	Supply and installation of Mild steel grating cover with frame on drain including all fittings for complete installation of following clear widths.6" wide L1 1 1/2" x1 1/2"x1/4" thick L2 1 1/2" x1 1/2"x1/4" thick & 1/2" M/S bar @ 4" c/c.	Rft	140		

ITEM No.	DESCRIPTION	UNIT	QTY	UNIT RATE (Rs.)	TOTAL AMOUNT (Rs.)
(a)	(b)	(c)	(d)	(e)	(f)
17	Providing, erecting and fixing in position Car parking shed of size 18'x18' made of MS pipe including PVC PVDF membrane, cutting, welding painting of pipes with red oxide and deco paint etc. as per drawings and approved by the Engineer complete in all respects. (Note: The Contractor will submit shop drawings and design calculations of the offered fabric and MS pipe structure for approval of the Engineer before initiation of work).	Sft	7,020		
ELECTRICAL WORKS:					
Ref. Spec. No. 8001,8150,8220,8230					
18	Providing and installation of 30 Watt LED batten weatherproof type light, better or equivalent 0.9 P.F., 50,000 life hours, 4 feet length, including wiring, switches etc. complete in all respects. (For Car Parking Shade)	No.	20		
Total Cost - (Rs.)					
WALKWAY SHED & ABLUTION AERA SHED					
ITEM No.	DESCRIPTION	UNIT	QTY	UNIT RATE (Rs.)	TOTAL AMOUNT (Rs.)
(a)	(b)	(c)	(d)	(e)	(f)
A.	CIVIL WORKS:				
Ref. Spec. No. 1100, 2100, 2200, 2300, 3000, 6700					
1	Dismantling of existing walkway sheds & Ablution sheds made of MS pipes pillars, H-section beams and CGI sheet covering and stacking the dismantled material at designated places as per instructions of the Engineer complete in all respects.	Sft	524		
2	Providing, erecting and fixing in position walkways sheds made of MS pipes and PVC PVDF membrane with opacity of 750 g/sqm both sides coated, UV resistant, fire retardant including excavation for foundation, backfilling, cutting, welding painting of pipes with red oxide and deco paint etc. as per drawings complete in all respects. (Note: The Contractor will submit shop drawings and design calculations of the offered fabric and MS pipe structure for approval of the Engineer before initiation of work).	Sft	300		
3	Providing and fixing of parking shed consisting of CGI Sheet, tubular pipe frame (heavy) quality and circular columns including excavation for foundation, backfilling, cutting, welding painting of pipes with red oxide and deco paint etc. as per drawings complete in all respects.	Sft	256		
Sub Total Cost - A (Rs.)					
B.	ELECTRICAL WORKS:				

ITEM No.	DESCRIPTION	UNIT	QTY	UNIT RATE (Rs.)	TOTAL AMOUNT (Rs.)
(a)	(b)	(c)	(d)	(e)	(f)
	Ref. Spec. No. 8001,8150,8220,8230				
4	Providing and installation of 30 Watt LED batten weatherproof type light, better or equivalent 0.9 P.F., 50,000 life hours, 4 feet length, including wiring, switches etc. complete in all respects. (For Walkway Shed)	No.	6		
Sub Total Cost - B (Rs.)					
Total Cost - (Rs.)					

Payment Terms Accepted	Yes	No
Completion time in days		

Name & Title:
Company Name:
Signature:
Stamp
Date: