

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

JOB-1- ELECTRICAL WORKS

IT E M NO .	Su b- lin e	DESCRIPTION	UNIT	QTY	RATE	TOTAL
		GENERAL NOTE				
		Supply, installation, testing and commissioning of the following items of work, including all labour, tools, plant, accessories, etc. required for completion of each item as per specifications and as approved by the Engineer				
		LT CABLES (EARTHING)				
E1	a.	Supply and install 6 sq.mm PVC insulated single core	RFT	250		

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		600/1000V cable with copper conductor in already concealed PVC conduit.				
E2	b.	Supply and install 10 sq.mm PVC insulated single core 600/1000V cable with copper conductor in already concealed PVC conduit	RFT	250		
E3	c.	Supply and install 16 sq.mm PVC insulated single core 600/1000V cable with copper conductor in already concealed PVC conduit.	RFT	250		
E4	d.	Supply and install 25 sq.mm PVC insulated single core 600/1000V cable with copper conductor in already concealed PVC conduit	RFT	250		
E5	e.	Supply and install 35 sq.mm PVC insulated single core 600/1000V cable with copper	RFT	250		

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		conductor in already concealed PVC conduit				
E6	f.	Supply and install 50 sq.mm PVC insulated single core 600/1000V cable with copper conductor in already concealed PVC conduit	RFT	250		
E7	g.	Supply and install 70 sq.mm PVC insulated single core 600/1000V cable with copper conductor in already concealed PVC conduit	RFT	250		
		NON-SCHEDULED ITEMS				
		LT DISTRIBUTION BOARD				
		LT 415V AC Main DB/Sub-Main DBs shall be made from 14 SWG sheet steel, while all other DBs must be				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

	<p>of 16SWG. This shall be designed, fabricated and manufactured as a free standing floor type. The sheet metal work shall be cleaned down to bare shining metal degreased, derusted and painted with TWO base coats of antirust RED paint. The sheet metal work shall be finished in TWO coats of powder paint. The color and shade shall be as approved by the Engineer. The distribution Board shall be complete with all internal wirings, tags, identification labels, TPN and E copper busbars, accessories etc. The DB should be provided with the armored glands. The busbars shall be insulated in RED, YELLOW, BLUE and BLACK insulations. The insulation shall be heat</p>				
--	---	--	--	--	--

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		shrinkable type or as directed by the Engineer.				
--	--	---	--	--	--	--

JOB-2-- MAIN ATS PANEL

ITEM NO.	Sub-line	DESCRIPTION	UNIT	QTY	RATE	TOTAL
		INCOMING (MAIN SUPPLY)				
		01 No. 150 Amps FP Adjustable MCCB (RC-36KA) 01 No. 300 Amps FP Adjustable MCCB (RC-36KA) 01 Nos. Complete Set of Synchronization panel 03 Nos. 2 Amps Protection fuses. 01 No. VSS (RY-YB-BR-OFF-RN-YN-BN) 01 No. Digital Voltmeter 01 No. ASS (4 position) 01 No. Digital Ampere Meter 03 No. 300/5A Current Transformers 03 No. 150/5A Current Transformers				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		01 No. 4 Pole Surge Protection Device 03 Nos. R-Y-B Indication lamps 03 Nos. Cu Bus Bars complete with Nut & bolts, washers/ insulation. 01 Nos. Earth Bus Bar 01 Nos. Neutral Bus Bar				
		OUTGOINGS				
		01 Nos. 630 Amps FP ADJ.MCCB RC-15KA 02 Nos. 250 Amps FP ADJ.MCCB RC-15KA	JOB	1		

JOB-3- MAIN DB

ITEMNO.	Sub- line	DESCRIPTION	UNIT	QTY	RATE	TOTAL
		INCOMING (MAIN SUPPLY)				
		02 No. 630 Amps FP ADJ.MCCB (RC-25KA) 01 Nos. Complete Set of ATS with Mechanical				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		interlocking including Magnetic contactors 03 Nos. 2 Amps Protection fuses. 01 No. VSS (RY-YB-BR- OFF-RN-YN-BN) 01 No. Digital Voltmeter 01 No. ASS (4 position) 01 No. Digital Ampere Meter 06 No. 630/5A Current Transformers 01 No. 4 Pole Surge Protection Device 03 Nos. R-Y-B Indication lamps 03 Nos. Cu Bus Bars complete with Nut & bolts, washers/ insulation. 01 Nos. Earth Bus Bar 01 Nos. Neutral Bus Bar				
		OUTGOINGS				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		04 Nos. 250 Amps FP ADJ.MCCB RC-15KA	JOB	1		

JOB-4-MAIN BUILDING

ITEM NO.	Sub- line	DESCRIPTION	UNIT	QTY	RATE	TOTAL
		01 Nos. 250 Amps FP ADJ.MCCB RC-15KA 03 Nos. 2 Amps Protection fuses. 01 No. VSS (RY-YB-BR- OFF-RN-YN-BN) 01 No. Emergency push button with shunt release coil 01 No. ASS (4 position) 01 No. Digital Ampere Meter 01 No. Digital Volt Meter 03 No. 250/5A Current Transformers				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		01 No. 4 Pole Surge Protection Device 03 Nos. R-Y-B Indication lamps 03 Nos. Cu Bus Bars complete with Nut & bolts, washers/ insulation. 01 Nos. Earth Bus Bar 01 Nos. Neutral Bus Bar				
		OUTGOINGS				
		03 Nos. 100 Amps TP MCB RC-6KA. 03 Nos. 60 Amps TP MCB RC-6KA	JOB	1		

JOB-5. RS OFFICE

ITEM NO.	Sub-line	DESCRIPTION	UNIT	QTY	RATE	TOTAL
-----------------	-----------------	--------------------	-------------	------------	-------------	--------------

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		INCOMING (MAIN SUPPLY)				
		01 Nos. 250 Amps FP ADJ.MCCB RC-15KA 03 Nos. 2 Amps Protection fuses. 01 No. VSS (RY-YB-BR- OFF-RN-YN-BN) 01 No. Emergency push button with shunt release coil 01 No. ASS (4 position) 01 No. Digital Ampere Meter 01 No. Digital Volt Meter 03 No. 250/5A Current Transformers 01 No. 4 Pole Surge Protection Device 03 Nos. R-Y-B Indication lamps 03 Nos. Cu Bus Bars complete with Nut & bolts, washers/ insulation. 01 Nos. Earth Bus Bar				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		01 Nos. Neutral Bus Bar				
		OUTGOINGS				
		01 Nos. 32 Amps DP MCB RC-6KA. 02 Nos. 100 Amps TP MCB RC-6KA. 02 Nos. 60 Amps TP MCB RC-6KA.	JOB	1		

JOB-6-PROTECTION OFFICE

ITEMNO.	Sub- line	DESCRIPTION	UNIT	QTY	RATE	TOTAL
		INCOMING (MAIN SUPPLY)				
		01 Nos. 250 Amps FP ADJ.MCCB RC-15KA 03 Nos. 2 Amps Protection fuses. 01 No. VSS (RY-YB- BR-OFF-RN-YN-BN)				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		01 No. Emergency push button with shunt release coil 01 No. ASS (4 position) 01 No. Digital Ampere Meter 01 No. Digital Volt Meter 03 No. 250/5A Current Transformers 01 No. 4 Pole Surge Protection Device 03 Nos. R-Y-B Indication lamps 03 Nos. Cu Bus Bars complete with Nut & bolts, washers/ insulation. 01 Nos. Earth Bus Bar 01 Nos. Neutral Bus Bar				
		OUTGOINGS				
		01 Nos. 32 Amps DP MCB RC-6KA. 02 Nos. 100 Amps TP MCB RC-6KA.	JOB	1		

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		04 Nos. 60 Amps TP MCB RC-6KA.				

JOB-7- GUEST HOUSE# 1& 2

ITEMNO.	Sub-line	DESCRIPTION	UNIT	QTY	RATE	TOTAL
		INCOMING (MAIN SUPPLY)				
		02 Nos. 250 Amps FP ADJ.MCCB RC-15KA 01 Nos. Complete Set of ATS with Mechanical interlocking including Magnetic contactors 03 Nos. 2 Amps Protection fuses. 01 No. VSS (RY- YB-BR-OFF-RN- YN-BN)				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		01 No. Emergency push button with shunt release coil 01 No. ASS (4 position) 01 No. Digital Ampere Meter 01 No. Digital Voltmeter 06 No. 250/5A Current Transformers 01 No. 4 Pole Surge Protection Device 03 Nos. R-Y-B Indication lamps 03 Nos. Cu Bus Bars complete with Nut & bolts, washers/ insulation. 01 Nos. Earth Bus Bar 01 Nos. Neutral Bus Bar				
--	--	--	--	--	--	--

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		OUTGOINGS				
		01 Nos. 63 Amps DP MCB RC-6KA. 05 Nos. 100 Amps TP MCB RC-6KA. 02 Nos. 60 Amps TP MCB RC-6KA.	JOB	1		

JOB-8- ATS PANEL 2

ITEMNO.	Sub-line	DESCRIPTION	UNIT	QTY	RATE	TOTAL
		INCOMING (MAIN SUPPLY)				
		02 Nos. 250 Amps FP ADJ.MCCB RC- 15KA 01 Nos. Complete Set of ATS with Mechanical interlocking				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		including Magnetic contactors 03 Nos. 2 Amps Protection fuses. 01 No. VSS (RY-YB-BR-OFF-RN-YN-BN) 01 No. Digital Voltmeter 01 No. ASS (4 position) 01 No. Digital Ampere Meter 01 No. 4 Pole Surge Protection Device 03 Nos. R-Y-B Indication lamps 03 Nos. Cu Bus Bars complete with Nut & bolts, washers/insulation. 01 Nos. Earth Bus Bar				
--	--	---	--	--	--	--

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		01 Nos. Neutral Bus Bar				
		OUTGOINGS				
		01 Nos. 250 Amps FP ADJ.MCCB RC-6KA	JOB	1		

JOB-9- GUEST HOUSE# 3

ITEMNO.	Sub-line	DESCRIPTION	UNIT	QTY	RATE	TOTAL
		INCOMING (MAIN SUPPLY)				
		02 Nos. 250 Amps FP ADJ.MCCB RC-15KA 01 Nos. Complete Set of ATS with Mechanical interlocking including Magnetic contactors				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		<p>03 Nos. 2 Amps Protection fuses. 01 No. VSS (RY-YB-BR-OFF-RN-YN-BN) 01 No. Emergency push button with shunt release coil 01 No. ASS (4 position) 01 No. Digital Ampere Meter 01 No. Digital Voltmeter 06 No. 250/5A Current Transformers 01 No. 4 Pole Surge Protection Device 03 Nos. R-Y-B Indication lamps 03 Nos. Cu Bus Bars complete with Nut & bolts,</p>				
--	--	---	--	--	--	--

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		washers/ insulation. 01 Nos. Earth Bus Bar 01 Nos. Neutral Bus Bar				
		OUTGOING				
		06 Nos. 100 Amps TP MCB RC-6KA. 02 Nos. 63 Amps TP MCB RC-6KA	JOB	1		

JOB-10 AUTOMATIC POWER FACTOR IMPROVEMENT PANEL

ITEMNO.	Sub-line	DESCRIPTION	UNIT	QTY	RATE	TOTAL
		Providing, Installing and commissioning of the following 3 Phase automatic power factor improvement panel	JOB	1		

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		<p>of 200 KVAR to be installed adjacent to LT Panel comprising of all necessary sensing and switching relays, contactors, banks of capacitors suitable for operation of 440V, 50Hz Control Voltage 230V, 50Hz Switching in and out the capacitors in 12 steps. 12 stage reactive power control relay with digital switch Manual/Auto/OFF Indication lamps, push button HRC fuses of suitable rating, contactors for capacitors, control fuses,</p>				
--	--	--	--	--	--	--

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		auxillary contactors for capacitors all necessary materials complete in all respects and as per general specifications.				
		NOTE: Cable Glands should be of non-magnetic material i.e. Stainless Steel or Aluminum				

JOB-11- LT CABLES

ITEMNO.	Sub-line	DESCRIPTION	UNIT	QTY	RATE	TOTAL
		Supply at site, installation, testing and commissioning of PVC insulated				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		<p>copper conductor cable 600 / 1000 Volt grade in prelaidd conduits / trenches / cable trays to be installed as per routes shown on drawings including cost of all necessary materials, connections, identification tags, cables lugs properly crimped at both ends for the following sizes complete in all accessories and in all respects as mentioned in Specification. Actual length of cables to be installed shall be practically</p>				
--	--	--	--	--	--	--

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		<p>measured at site by the Contractor, duly authenticated by the Engineer before placing the order with the manufacturer, however, approximate length of cables are shown herewith. Payments shall be made as per actual length installed. Contractor should provide shop drawings before installation and have to get approval from Client / Consultant/Site incharge.</p>				
E-10	i	120 sqmm, 4 core CU/XLPE/PVC	^{RFT}	400		

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		stranded copper conductor cable, 600/1000 V grade in already installed conduit/on cable tray.				
E-11	ii	70 sqmm, 4 core CU/XLPE/PVC stranded copper conductor cable, 600/1000 V grade in already installed conduit/on cable tray.	RFT	250		
E-12	iii	25 sqmm, 4 core CU/PVC/PVC stranded copper conductor cable, 600/1000 V grade in already installed conduit/on cable tray.	RFT	150		
E-13	iv	35 sqmm, 4 core CU/PVC/PVC	RFT	150		

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		stranded copper conductor cable, 600/1000 V grade in already installed conduit/on cable tray.				
E-14	V	16 sqmm, 4 core CU/PVC/PVC stranded copper conductor cable, 600/1000 V grade in already installed conduit/on cable tray.	RFT	150		
E-15	VI	10 sqmm, 4 core CU/PVC/PVC stranded copper conductor cable, 600/1000V grade in already installed conduit/on cable tray .	RFT	150		
E-16	VII	50 sqmm, 1 core CU/PVC/PVC	RFT	450		

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		stranded copper conductor cable, 600/1000V grade in already installed conduit/on cable tray .				
E-17	VIII	70 sqmm, 1 core CU/PVC/PVC stranded copper conductor cable, 600/1000V grade in already installed conduit/on cable tray .	RFT	450		
E-18	IX	95 sqmm, 1 core CU/PVC/PVC stranded copper conductor cable, 600/1000V grade in already installed conduit/on cable tray .	RFT	450		

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

E-19	X	120 sqmm, 1 core CU/PVC/PVC stranded copper conductor armoured cable, 600/1000V grade in already installed conduit/on cable tray	RFT	450		
E-20	XI	185 sqmm, 1 core CU/PVC/PVC stranded copper conductor armoured cable, 600/1000V grade in already installed conduit/on cable tray .	RFT	550		
		GENERAL NOTE Supply, installation, testing and commissioning of the following				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		items of work, including all labour, tools, plant, accessories, etc. required for completion of each item as per specifications and as approved by the Engineer				

JOB-12-LT CABLES (EARTHING)

ITEM NO.	Sub-line	DESCRIPTION	UNIT	QTY	RATE	TOTAL
-----------------	-----------------	--------------------	-------------	------------	-------------	--------------

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

E-1	i.	Supply and install 6 sq.mm PVC insulated single core 600/1000V cable with copper conductor in already concealed PVC conduit	RFT	250		
E-2	ii.	Supply and install 10 sq.mm PVC insulated single core 600/1000V cable with copper conductor in already concealed PVC conduit	RFT	250		
E-3	iii.	Supply and install 16 sq.mm PVC insulated single core 600/1000V cable with copper conductor in already concealed PVC conduit	RFT	250		

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

E-4	Iv	Supply and install 25 sq.mm PVC insulated single core 600/1000V cable with copper conductor in already concealed PVC conduit	RFT	250		
E-5	V	Supply and install 35 sq.mm PVC insulated single core 600/1000V cable with copper conductor in already concealed PVC conduit.	RFT	250		
E-6	Vi	Supply and install 50 sq.mm PVC insulated single core 600/1000V cable with copper conductor in	RFT	250		

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		already concealed PVC conduit				
E-7	VII	Supply and install 70 sq.mm PVC insulated single core 600/1000V cable with copper conductor in already concealed PVC conduit.	RFT	250		
		LT DISTRIBUTION BOARD				
		LT 415V AC Main DB/Sub-Main DBs shall be made from 14 SWG sheet steel, while all other DBs must be of 16SWG. This shall be designed, fabricated and manufactured as a				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		<p>free standing floor type. The sheet metal work shall be cleaned down to bare shining metal degreased, derusted and painted with TWO base coats of antirust RED paint. The sheet metal work shall be finished in TWO coats of powder paint. The color and shade shall be as approved by the Engineer. The distribution Board shall be complete with all internal wirings, tags, identification labels, TPN and E copper busbars, accessories etc.</p>				
--	--	---	--	--	--	--

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		The DB should be provided with the armored glands. The bus-bars shall be insulated in RED, YELLOW, BLUE and BLACK insulations. The insulation shall be heat shrinkable type or as directed by the Engineer.				

JOB-13- MAIN ATS PANEL

ITEM NO.	Sub-line	DESCRIPTION	UNIT	QTY	RATE	TOTAL
		INCOMING (MAIN SUPPLY)				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		<p>01 No. 200 Amps FP Adjustable MCCB (RC- 36KA)</p> <p>01 No. 350 Amps FP Adjustable MCCB (RC- 36KA)</p> <p>01 Nos. Complete Set of Synchronization panel</p> <p>03 Nos. 2 Amps Protection fuses.</p> <p>01 No. VSS (RY- YB-BR-OFF-RN- YN-BN)</p> <p>01 No. Digital Voltmeter</p> <p>01 No. ASS (4 position)</p> <p>01 No. Digital Ampere Meter</p>				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		03 No. 200/5A Current Transformers 03 No. 350/5A Current Transformers 01 No. 4 Pole Surge Protection Device 03 Nos. R-Y-B Indication lamps 03 Nos. Cu Bus Bars complete with Nut & bolts, washers/ insulation. 01 Nos. Earth Bus Bar 01 Nos. Neutral Bus Bar				
		OUTGOINGS				
		08 Nos. 250 Amps FP ADJ.MCCB RC-15KA	JOB	1		

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

--	--	--	--	--	--	--

JOB-14-MAIN DB

ITEMNO.	Sub-line	DESCRIPTION	UNIT	QTY	RATE	TOTAL
		INCOMING (MAIN SUPPLY)				
		01 No. 630 Amps FP ADJ.MCCB (RC-25KA) 03 Nos. 2 Amps Protection fuses. 01 No. VSS (RY- YB-BR-OFF-RN- YN-BN) 01 No. Digital Voltmeter 01 No. ASS (4 position) 01 No. Digital Ampere Meter				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		03 No. 630/5A Current Transformers 01 No. 4 Pole Surge Protection Device 03 Nos. R-Y-B Indication lamps 03 Nos. Cu Bus Bars complete with Nut & bolts, washers/ insulation. 01 Nos. Earth Bus Bar 01 Nos. Neutral Bus Bar				
		OUTGOINGS				
		04 Nos. 250 Amps FP ADJ.MCCB RC-15KA	JOB	1		

JOB-15-MAIN BUILDING

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

ITEM NO.	Sub-line	DESCRIPTION	UNIT	QTY	RATE	TOTAL
		INCOMING (MAIN SUPPLY)				
		02 Nos. 250 Amps FP ADJ.MCCB RC-15KA 01 Nos. Complete Set of ATS with Mechanical interlocking including Magnetic contactors 03 Nos. 2 Amps Protection fuses. 01 No. VSS (RY- YB-BR-OFF-RN- YN-BN) 01 No. Emergency push button with shunt release coil 01 No. ASS (4 position)				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		01 No. Digital Ampere Meter 01 No. Digital Volt Meter 06 No. 250/5A Current Transformers 01 No. 4 Pole Surge Protection Device 03 Nos. R-Y-B Indication lamps 03 Nos. Cu Bus Bars complete with Nut & bolts, washers/insulation. 01 Nos. Earth Bus Bar 01 Nos. Neutral Bus Bar				
		OUTGOINGS				
		03 Nos. 100 Amps TP MCB RC-6KA.	JOB	1		

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		03 Nos. 60 Amps TP MCB RC-6KA.				

JOB-16- RS OFFICE

ITEMNO.	Sub-line	DESCRIPTION	UNIT	QTY	RATE	TOTAL
		INCOMING (MAIN SUPPLY)				
		02 Nos. 250 Amps FP ADJ.MCCB RC-15KA 01 Nos. Complete Set of ATS with Mechanical interlocking including Magnetic contactors 03 Nos. 2 Amps Protection fuses.				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		01 No. VSS (RY-YB-BR-OFF-RN-YN-BN) 01 No. Emergency push button with shunt release coil 01 No. ASS (4 position) 01 No. Digital Ampere Meter 01 No. Digital Volt Meter 06 No. 250/5A Current Transformers 01 No. 4 Pole Surge Protection Device 03 Nos. R-Y-B Indication lamps 03 Nos. Cu Bus Bars complete with Nut & bolts, washers/insulation.				
--	--	--	--	--	--	--

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		01 Nos. Earth Bus Bar 01 Nos. Neutral Bus Bar				
		OUTGOINGS				
		01 Nos. 32 Amps DP MCB RC-6KA. 02 Nos. 100 Amps TP MCB RC-6KA. 02 Nos. 60 Amps TP MCB RC-6KA.	JOB	1		

JOB-17-PROTECTION OFFICE

ITEMNO.	Sub-line	DESCRIPTION	UNIT	QTY	RATE	TOTAL
		INCOMING (MAIN SUPPLY)				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		<p>02 Nos. 250 Amps FP ADJ.MCCB RC-15KA 01 Nos. Complete Set of ATS with Mechanical interlocking including Magnetic contactors 03 Nos. 2 Amps Protection fuses. 01 No. VSS (RY- YB-BR-OFF-RN- YN-BN) 01 No. Emergency push button with shunt release coil 01 No. ASS (4 position) 01 No. Digital Ampere Meter 01 No. Digital Volt Meter 06 No. 250/5A Current Transformers</p>			
--	--	--	--	--	--

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		<p>01 No. 4 Pole Surge Protection Device</p> <p>03 Nos. R-Y-B Indication lamps</p> <p>03 Nos. Cu Bus Bars complete with Nut & bolts, washers/insulation.</p> <p>01 Nos. Earth Bus Bar</p> <p>01 Nos. Neutral Bus Bar</p>				
		OUTGOINGS				
		<p>01 Nos. 32 Amps DP MCB RC-6KA.</p> <p>02 Nos. 100 Amps TP MCB RC-6KA.</p> <p>04 Nos. 60 Amps TP MCB RC-6KA.</p>	JOB	1		

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

JOB-18 GUEST HOUSE# 1& 2

ITEM NO.	Sub-line	DESCRIPTION	UNIT	QTY	RATE	TOTAL
		INCOMING (MAIN SUPPLY)				
		02 Nos. 250 Amps FP ADJ.MCCB RC-15KA 01 Nos. Complete Set of ATS with Mechanical interlocking including Magnetic contactors 03 Nos. 2 Amps Protection fuses. 01 No. VSS (RY- YB-BR-OFF-RN- YN-BN) 01 No. Emergency push button with shunt release coil				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		<p>01 No. ASS (4 position) 01 No. Digital Ampere Meter 01 No. Digital Voltmeter 06 No. 250/5A Current Transformers 01 No. 4 Pole Surge Protection Device 03 Nos. R-Y-B Indication lamps 03 Nos. Cu Bus Bars complete with Nut & bolts, washers/insulation. 01 Nos. Earth Bus Bar 01 Nos. Neutral Bus Bar</p>				
		OUTGOINGS				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		01 Nos. 63 Amps DP MCB RC-6KA. 05 Nos. 100 Amps TP MCB RC-6KA. 02 Nos. 60 Amps TP MCB RC-6KA	JOB	1		

JOB-19-ATS PANEL 2

ITEMNO.	Sub-line	DESCRIPTION	UNIT	QTY	RATE	TOTAL
		INCOMING (MAIN SUPPLY)				
		02 Nos. 250 Amps FP ADJ.MCCB RC-15KA 01 Nos. Complete Set of ATS with Mechanical interlocking				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		<p>including Magnetic contactors 03 Nos. 2 Amps Protection fuses. 01 No. VSS (RY-YB-BR-OFF-RN-YN-BN) 01 No. Digital Voltmeter 01 No. ASS (4 position) 01 No. Digital Ampere Meter 01 No. 4 Pole Surge Protection Device 03 Nos. R-Y-B Indication lamps 03 Nos. Cu Bus Bars complete with Nut & bolts, washers/insulation. 01 Nos. Earth Bus Bar</p>				
--	--	--	--	--	--	--

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		01 Nos. Neutral Bus Bar				
		OUTGOINGS				
		01 Nos. 250 Amps FP ADJ.MCCB RC-15KA	Job	1		

JOB-20-GUEST HOUSE# 3

ITEMNO.	Sub-line	DESCRIPTION	UNIT	QTY	RATE	TOTAL
		INCOMING (MAIN SUPPLY)				
		02 Nos. 250 Amps FP ADJ.MCCB RC-15KA 01 Nos. Complete Set of ATS with				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		<p>Mechanical interlocking including Magnetic contactors 03 Nos. 2 Amps Protection fuses. 01 No. VSS (RY-YB-BR-OFF-RN-YN-BN) 01 No. Emergency push button with shunt release coil 01 No. ASS (4 position) 01 No. Digital Ampere Meter 01 No. Digital Voltmeter 06 No. 250/5A Current Transformers 01 No. 4 Pole Surge Protection Device 03 Nos. R-Y-B Indication lamps</p>				
--	--	---	--	--	--	--

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		03 Nos. Cu Bus Bars complete with Nut & bolts, washers/ insulation. 01 Nos. Earth Bus Bar 01 Nos. Neutral Bus Bar				
		OUTGOING				
		06 Nos. 100 Amps TP MCB RC-6KA. 02 Nos. 63 Amps TP MCB RC-6KA	JOB	1		

JOB-21-AUTOMATIC POWER FACTOR IMPROVEMENT PANEL

ITEMNO.	Sub-line	DESCRIPTION	UNIT	QTY	RATE	TOTAL
			JOB	1		

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		<p>Providing, Installing and commissioning of the following 3 Phase automatic power factor improvement panel of 200KVAR to be installed adjacent to LT Panel comprising of all necessary sensing and switching relays, contactors, banks of capacitors suitable for operation of 440V, 50Hz Control Voltage 230V, 50Hz Switching in and out the capacitors in 12 steps. 12 stage reactive power control relay with digital switch</p>				
--	--	---	--	--	--	--

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		Manual/Auto/OFF Indication lamps, push button HRC fuses of suitable rating, contactors for capacitors, control fuses, auxillary contactors for capacitors all necessary materials complete in all respects and as per general specifications.				
		NOTE: Cable Glands should be of non-magnetic material i.e. Stainless Steel or Aluminum				

JOB-22-LT CABLES

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

ITEM NO.	Sub-line	DESCRIPTION	UNIT	QTY	RATE	TOTAL
		Supply at site, installation, testing and commissioning of PVC insulated copper conductor cable 600 / 1000 Volt grade in pre-laid conduits / trenches / cable trays to be installed as per routes shown on drawings including cost of all necessary materials, connections, identification tags, cables lugs properly crimped at both ends for the following sizes				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		<p>complete in all accessories and in all respects as mentioned in Specification. Actual length of cables to be installed shall be practically measured at site by the Contractor, duly authenticated by the Engineer before placing the order with the manufacturer, however, approximate length of cables are shown herewith. Payments shall be made as per actual length installed. Contractor should provide shop drawings before</p>				
--	--	---	--	--	--	--

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		installation and have to get approval from Client / Consultant/Site incharge.				
		120 sqmm, 4 core CU/XLPE/PVC stranded copper conductor cable, 600/1000 V grade in already installed conduit/on cable tray.	RFT	400		
		70 sqmm, 4 core CU/XLPE/PVC stranded copper conductor cable, 600/1000 V grade in already installed conduit/on cable tray.	RFT	250		
		25 sqmm, 4 core CU/PVC/PVC	RFT	150		

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		stranded copper conductor cable, 600/1000 V grade in already installed conduit/on cable tray.				
		35 sqmm, 4 core CU/PVC/PVC stranded copper conductor cable, 600/1000 V grade in already installed conduit/on cable tray	RFT	150		
		16 sqmm, 4 core CU/PVC/PVC stranded copper conductor cable, 600/1000 V grade in already installed conduit/on cable tray.	RFT	150		

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		10 sqmm, 4 core CU/PVC/PVC stranded copper conductor cable, 600/1000V grade in already installed conduit/on cable tray .	RFT	150		
		50 sqmm, 1 core CU/PVC/PVC stranded copper conductor cable, 600/1000V grade in already installed conduit/on cable tray .	RFT	450		
		70 sqmm, 1 core CU/PVC/PVC stranded copper conductor cable, 600/1000V grade in already installed conduit/on cable tray .	RFT	450		

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		95 sqmm, 1 core CU/PVC/PVC stranded copper conductor cable, 600/1000V grade in already installed conduit/on cable tray	RFT	450		
		120 sqmm, 1 core CU/PVC/PVC stranded copper conductor armoured cable, 600/1000V grade in already installed conduit/on cable tray .	RFT	450		
		185 sqmm, 1 core CU/PVC/PVC stranded copper conductor armoured cable, 600/1000V grade	RFT	550		

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		in already installed conduit/on cable tray				

JOB-23-ELECTRICAL WORKS

ITEM NO.	Sub-line	DESCRIPTION	UNIT	QTY	RATE	TOTAL
		GENERAL NOTE				
		Supply, installation, testing and commissioning of the following items of work, including all labour, tools, plant, accessories, etc. required for completion of each item as per specifications and				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		as approved by the Engineer.				
		CONDUITS, PIPES & CABLE TRAY				
E-1		Providing and fixing 4" deep cable tray with straight flange fabricated with perforated G.I. Sheet of specified guage,size and depth duly wall supported/ceiling hung,supported on painted brackets of MS angle iron of 1-1/2"x1-1/2"x3/16" and MS patti of 1-1/2"x3/16" size @ 5 ft C/C, hangers i/c the cost of hardwares as approved and				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		directed by the Engineer Incharge				
		18"x4"	P.RFT	700		
		9"x4"	P.RFT	550		
		Supply and installation of 2"(50mm) dia PVC concealed conduit including all accessories such as bends, elbows etc	RFT	100		
		Supply and installation of 1.5"(40mm) dia PVC concealed conduit including all accessories such as bends, elbows etc.	RFT	250		
		Supply and installation of	RFT	1000		

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		1"(25mm) dia PVC concealed conduit including all accessories such as bends, elbows etc				
		Supply and installation of 16x16mm duct including all accessories	RFT	1000		
		Supply and installation of 25x25mm duct including all accessories	RFT	650		
		Supply and installation of 40x40mm duct including all accessories	RFT	350		

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

JOB-24- 400 KVA & 100 KVA TRANSFORMER:

ITEMNO.	Sub-line	DESCRIPTION	UNIT	QTY	RATE	TOTAL
		Supply, Installation, commissioning and Testing of 400KVA & 100KVA 11/0.415KV Oil immersed IP66 QESCO/WAPDA/NTDC approved Transformer to be Installed inside the transformer room with Transformer Mounting PAD including construction of mounting pad and all accessories complete in all respects as mentioned in Specification.	NO	1		
		Note: Contractor will ensure that design book for QESCO/WAPDA/NTDC				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		endorse 400KVA & 100KVA Transformer only. Moreover, contractor will start procurement of Transformer after approval of QESCO/WAPDA/NTDC design book mentioned in part 13.				
		Shifting of already installed 100KVA transformer from one building to another (this includes Grid sharing cost, cost of feeder, Rehabilitation charges, Capital cost, Security cost, Feeder installation and commissioning cost and right of way charges etc.. Complete in all respect.)	JOB	1		

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		Note: All Demand notices shall be paid by client				

JOB-25--EARTHING SYSTEM

ITEMNO.	Sub-line	DESCRIPTION	UNIT	QTY	RATE	TOTAL
		Supply, Installation, Testing and commissioning of following earthing system including all accessories complete in all respects and as mentioned in Specification				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		<p>Drilling of earth bore 80 to 90 ft. deep or up to permanent water table, back filling, ramming, complete in all respect including cost of copper rod dia 3/4" length 3000mm or as shown in the drawing fixing of 70mm copper wire in 1" GI conduit up to ecp complete in all respect as required. Earthing bores shall be made at 2000mm away from foundation and distance between earth bore shall not be less than 3000mm</p>	NO	7		

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		Man Hole for Earthing	NO	7		
		25 sqmm, 1 core CU stranded conductor bare (for Earthing).	RFT	100		
		95 sqmm, 1 core CU stranded conductor bare (for Earthing).	RFT	350		
		305 mm long, 50 mm wide and 6mm thick copper busbar as ECP (Earth Connecting Point) complete with insulators, washers, nuts, bolts mounting installation and operational	NO	7		

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		accessories as per site requirements.				
--	--	---------------------------------------	--	--	--	--

JOB-26-WIRING IN CONCEALED CONDUITS

ITEM NO.	Sub-line	DESCRIPTION	UNIT	QTY	RATE	TOTAL
		Supply, installation, and testing of Wiring of circuit from Distribution Board to Power socket , 230 Volts, with Three nos. single core 6 sqmm PVC insulated 450/750 Volts grade stranded copper conductor cables in 1" dia Concealed/open PVC conduit laid underfloor / wall including PVC conduit, conduit accessories, etc. all accessories complete in	NO	25		

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		all respects and as mentioned in Specification.(Excluding cost of pipe and socket)				
		Supply, installation, and testing of Wiring of circuit from Distribution Board to Power socket , 230 Volts, with Three nos. single core 4 sqmm PVC insulated 450/750 Volts grade stranded copper conductor cables in 1" dia Concealed/open PVC conduit laid underfloor / wall including PVC conduit, conduit accessories, etc. all accessories complete in all respects and as mentioned in Specification.(Excluding cost of pipe and socket)	NO	150		

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		GENERAL NOTE				
		Supply, installation, testing and commissioning of the following items of work, including all labour, tools, plant, accessories, etc. required for completion of each item as per specifications and as approved by the Engineer				

JOB-27-LT DISTRIBUTION BOARD

ITEMNO.	Sub-line	DESCRIPTION	UNIT	QTY	RATE	TOTAL
		LT 415V AC Main DB/Sub-Main DBs shall be made from				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		<p>14 SWG sheet steel, while all other DBs must be of 16SWG. This shall be designed, fabricated and manufactured as a free standing floor type. The sheet metal work shall be cleaned down to bare shining metal degreased, derusted and painted with TWO base coats of antirust RED paint. The sheet metal work shall be finished in TWO coats of powder paint. The color and shade shall be as approved by the Engineer. The distribution Board</p>				
--	--	---	--	--	--	--

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		<p>shall be complete with all internal wirings, tags, identification labels, TPN and E copper busbars, accessories etc. The DB should be provided with the armored glands. The bus-bars shall be insulated in RED, YELLOW, BLUE and BLACK insulations. The insulation shall be heat shrinkable type or as directed by the Engineer.</p>				
A		DB-AC & Power - GF				
		INCOMING (MAIN DB)				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		<p>01 No. 100 Amps TP MCCB RC- 10KA 03 Nos. 2 Amps Protection fuses. 01 No. VSS (RY- YB-BR-OFF-RN- YN-BN) 01 No. ASS (4 position) 01 No. Digital Ampere Meter 01 No. Digital Volt Meter 03 No. 100/5A Current Transformers 03 Nos. R-Y-B Indication lamps 03 Nos. Cu Bus Bars complete with Nut & bolts, washers/ insulation.</p>				
--	--	---	--	--	--	--

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		01 Nos. Earth Bus Bar 01 Nos. Neutral Bus Bar				
		OUTGOINGS				
B		8 Nos. 20 Amps SP MCB RC-6KA 15 Nos. 16 Amps SP MCB RC-6KA	JOB	1		
		DB-AC & POWER-RT				
		INCOMING (MAIN DB)				
		01 Nos. 60 Amps TP MCCB RC-10KA 03 Nos. 2 Amps Protection fuses. 01 No. VSS (RY-YB-BR-OFF-RN-YN-BN) 01 No. ASS (4 position)				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		01 No. Digital Ampere Meter 01 No. Digital Volt Meter 03 No. 60/5A Current Transformers 03 Nos. R-Y-B Indication lamps 03 Nos. Cu Bus Bars complete with Nut & bolts, washers/insulation. 01 Nos. Earth Bus Bar 01 Nos. Neutral Bus Bar				
		OUTGOINGS				
		06 Nos. 20 Amps SP MCB RC-6KA. 08 Nos. 16 Amps SP MCB RC-6KA	JOB	1		

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

C		DB-AC & POWER-1F				
		INCOMING (MAIN DB)				
		01 Nos. 100 Amps TP MCCB RC- 10KA 03 Nos. 2 Amps Protection fuses. 01 No. VSS (RY- YB-BR-OFF-RN- YN-BN) 01 No. ASS (4 position) 01 No. Digital Ampere Meter 01 No. Digital Volt Meter 03 No. 100/5A Current Transformers 03 Nos. R-Y-B Indication lamps				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		03 Nos. Cu Bus Bars complete with Nut & bolts, washers/ insulation. 01 Nos. Earth Bus Bar 01 Nos. Neutral Bus Bar				
		OUTGOINGS				
		09 Nos. 20 Amps SP MCB RC-6KA. 17 Nos. 16 Amps SP MCB RC-6KA	Job	1		
		WIRING IN CONCEALED CONDUITS				
		Supply, installation, and testing of Wiring of circuit from Distribution Board to Power socket for AC and heater ,	No	17		

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		230 Volts, with Three nos. single core 6 sqmm PVC insulated 450/750 Volts grade stranded copper conductor cables in 1" dia Concealed/open PVC conduit laid underfloor / wall including PVC conduit, conduit accessories, etc. all accessories complete in all respects and as mentioned in Specification.				
--	--	---	--	--	--	--

ITEMNO.	Sub-line	DESCRIPTION	UNIT	QTY	RATE	TOTAL
		GENERAL NOTE				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		Supply, installation, testing and commissioning of the following items of work, including all labour, tools, plant, accessories, etc. required for completion of each item as per specifications and as approved by the Engineer				
		LT DISTRIBUTION BOARD				
		LT 415V AC Main DB/Sub-Main DBs shall be made from 14 SWG sheet steel, while all other DBs must be of 16SWG. This shall be designed,				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		<p>fabricated and manufactured as a free standing floor type. The sheet metal work shall be cleaned down to bare shining metal degreased, derusted and painted with TWO base coats of antirust RED paint. The sheet metal work shall be finished in TWO coats of powder paint. The color and shade shall be as approved by the Engineer. The distribution Board shall be complete with all internal wirings, tags, identification labels, TPN and E</p>				
--	--	---	--	--	--	--

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		<p>copper busbars, accessories etc. The DB should be provided with the armored glands. The bus-bars shall be insulated in RED, YELLOW, BLUE and BLACK insulations. The insulation shall be heat shrinkable type or as directed by the Engineer.</p>				
		DB-AC & Power - BF				
		INCOMING (MAIN DB)				
		01 No. 60 Amps TP MCCB RC-10KA				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		03 Nos. 2 Amps Protection fuses. 01 No. VSS (RY-YB-BR-OFF-RN-YN-BN) 01 No. ASS (4 position) 01 No. Digital Ampere Meter 01 No. Digital Volt Meter 03 No. 60/5A Current Transformers 03 Nos. R-Y-B Indication lamps 03 Nos. Cu Bus Bars complete with Nut & bolts, washers/insulation. 01 Nos. Earth Bus Bar 01 Nos. Neutral Bus Bar				
--	--	--	--	--	--	--

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		OUTGOINGS				
		4 Nos. 16 Amps SP MCB RC-6KA				
		3 Nos. 20 Amps SP MCB RC-6KA	Job	1		
		DB-AC & POWER-GF				
		INCOMING (MAIN DB)				
		01 Nos. 100 Amps TP MCCB RC- 10KA 03 Nos. 2 Amps Protection fuses. 01 No. VSS (RY- YB-BR-OFF-RN- YN-BN) 01 No. ASS (4 position) 01 No. Digital Ampere Meter				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		01 No. Digital Volt Meter 03 No. 100/5A Current Transformers 03 Nos. R-Y-B Indication lamps 03 Nos. Cu Bus Bars complete with Nut & bolts, washers/insulation. 01 Nos. Earth Bus Bar 01 Nos. Neutral Bus Bar				
		OUTGOINGS				
		08 Nos. 20 Amps SP MCB RC-6KA. 20 Nos. 16 Amps SP MCB RC-6KA	Job	1		
		DB-AC & POWER-1F				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		INCOMING (MAIN DB)				
		01 Nos. 100 Amps TP MCCB RC- 10KA 03 Nos. 2 Amps Protection fuses. 01 No. VSS (RY- YB-BR-OFF-RN- YN-BN) 01 No. ASS (4 position) 01 No. Digital Ampere Meter 01 No. Digital Volt Meter 03 No. 100/5A Current Transformers 03 Nos. R-Y-B Indication lamps 03 Nos. Cu Bus Bars complete with Nut & bolts,				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		washers/ insulation. 01 Nos. Earth Bus Bar 01 Nos. Neutral Bus Bar				
		OUTGOINGS				
		1 Nos. 25 Amps SP MCB RC-6KA. 8 Nos. 20 Amps SP MCB RC-6KA. 18 Nos. 16 Amps SP MCB RC-6KA.	Job	1		
		DB-AC & POWER-RT				
		INCOMING (MAIN DB)				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		<p>01 Nos. 60 Amps TP MCCB RC- 10KA 03 Nos. 2 Amps Protection fuses. 01 No. VSS (RY- YB-BR-OFF-RN- YN-BN) 01 No. ASS (4 position) 01 No. Digital Ampere Meter 01 No. Digital Volt Meter 03 No. 60/5A Current Transformers 03 Nos. R-Y-B Indication lamps 03 Nos. Cu Bus Bars complete with Nut & bolts, washers/ insulation. 01 Nos. Earth Bus Bar</p>				
--	--	--	--	--	--	--

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		01 Nos. Neutral Bus Bar				
		OUTGOINGS				
		05 Nos. 20 Amps SP MCB RC-6KA. 08 Nos. 16 Amps SP MCB RC-6KA.				
		WIRING IN CONCEALED CONDUITS				
		Supply, installation, and testing of Wiring of circuit from	No	20		

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		<p>Distribution Board to Power socket for AC and heater , 230 Volts, with Three nos. single core 6 sqmm PVC insulated 450/750 Volts grade stranded copper conductor cables in 1" dia Concealed/open PVC conduit laid underfloor / wall including PVC conduit, conduit accessories, etc. all accessories complete in all respects and as mentioned in Specification</p>				
		GENERAL NOTE				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		Supply, installation, testing and commissioning of the following items of work, including all labour, tools, plant, accessories, etc. required for completion of each item as per specifications and as approved by the Engineer.				
		LT DISTRIBUTION BOARD				
		LT 415V AC Main DB/Sub-Main DBs shall be made from 14 SWG sheet steel, while all other DBs must be of 16SWG. This shall be designed,				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		<p>fabricated and manufactured as a free standing floor type. The sheet metal work shall be cleaned down to bare shining metal degreased, derusted and painted with TWO base coats of antirust RED paint. The sheet metal work shall be finished in TWO coats of powder paint. The color and shade shall be as approved by the Engineer. The distribution Board shall be complete with all internal wirings, tags, identification labels, TPN and E</p>				
--	--	---	--	--	--	--

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		<p>copper busbars, accessories etc. The DB should be provided with the armored glands. The bus-bars shall be insulated in RED, YELLOW, BLUE and BLACK insulations. The insulation shall be heat shrinkable type or as directed by the Engineer.</p>				
		DB-AC & Power - GF				
		INCOMING (MAIN DB)				
		01 No. 100 Amps TP MCCB RC-10KA				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		03 Nos. 2 Amps Protection fuses. 01 No. VSS (RY-YB-BR-OFF-RN-YN-BN) 01 No. ASS (4 position) 01 No. Digital Ampere Meter 01 No. Digital Volt Meter 03 No. 100/5A Current Transformers 03 Nos. R-Y-B Indication lamps 03 Nos. Cu Bus Bars complete with Nut & bolts, washers/insulation. 01 Nos. Earth Bus Bar 01 Nos. Neutral Bus Bar				
--	--	---	--	--	--	--

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		OUTGOINGS				
		5 Nos. 20 Amps SP MCB RC-6KA 10 Nos. 16 Amps SP MCB RC-6KA				
		DB-AC & POWER-1F				
		INCOMING (MAIN DB)				
		01 Nos. 100 Amps TP MCCB RC- 10KA 03 Nos. 2 Amps Protection fuses. 01 No. VSS (RY- YB-BR-OFF-RN- YN-BN) 01 No. ASS (4 position) 01 No. Digital Ampere Meter				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		<p>01 No. Digital Volt Meter</p> <p>03 No. 60/5A Current Transformers</p> <p>03 Nos. R-Y-B Indication lamps</p> <p>03 Nos. Cu Bus Bars complete with Nut & bolts, washers/insulation.</p> <p>01 Nos. Earth Bus Bar</p> <p>01 Nos. Neutral Bus Bar</p>				
		OUTGOINGS				
		<p>06 Nos. 20 Amps SP MCB RC-6KA</p> <p>10 Nos. 16 Amps SP MCB RC-6KA</p>	Job	1		
		WIRING IN CONCEALED CONDUITS				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		<p>Supply, installation, and testing of Wiring of circuit from Distribution Board to Power socket for AC and heater , 230 Volts, with Three nos. single core 6 sqmm PVC insulated 450/750 Volts grade stranded copper conductor cables in 1" dia Concealed/open PVC conduit laid underfloor / wall including PVC conduit, conduit accessories, etc. all accessories complete in all respects and as mentioned in Specification.</p>	<p>No</p>	<p>7</p>		
--	--	---	-----------	-----------------	--	--

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

ITEM NO.	Sub-line	DESCRIPTION	UNIT	QTY	RATE	TOTAL
		GENERAL NOTE Supply, installation, testing and commissioning of the following items of work, including all labour, tools, plant, accessories, etc. required for completion of each item as per specifications and as approved by the Engineer				
		LT DISTRIBUTION BOARD LT 415V AC Main DB/Sub-Main DBs shall be made from				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		<p>14 SWG sheet steel, while all other DBs must be of 16SWG. This shall be designed, fabricated and manufactured as a free standing floor type. The sheet metal work shall be cleaned down to bare shining metal degreased, derusted and painted with TWO base coats of antirust RED paint. The sheet metal work shall be finished in TWO coats of powder paint. The color and shade shall be as approved by the Engineer. The distribution Board</p>				
--	--	---	--	--	--	--

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		<p>shall be complete with all internal wirings, tags, identification labels, TPN and E copper busbars, accessories etc. The DB should be provided with the armored glands. The bus-bars shall be insulated in RED, YELLOW, BLUE and BLACK insulations. The insulation shall be heat shrinkable type or as directed by the Engineer.</p>				
		DB-AC & Power - BF				
		INCOMING (MAIN DB)				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		<p>01 No. 100 Amps TP MCCB RC- 10KA 03 Nos. 2 Amps Protection fuses. 01 No. VSS (RY- YB-BR-OFF-RN- YN-BN) 01 No. ASS (4 position) 01 No. Digital Ampere Meter 01 No. Digital Volt Meter 03 No. 100/5A Current Transformers 03 Nos. R-Y-B Indication lamps 03 Nos. Cu Bus Bars complete with Nut & bolts, washers/ insulation.</p>				
--	--	---	--	--	--	--

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		01 Nos. Earth Bus Bar 01 Nos. Neutral Bus Bar				
		OUTGOINGS				
		13 Nos. 20 Amps SP MCB RC-6KA 20 Nos. 16 Amps SP MCB RC-6KA	Job	1		
		DB-AC & POWER-MF				
		INCOMING (MAIN DB)				
		01 Nos. 60 Amps TP MCCB RC-10KA 03 Nos. 2 Amps Protection fuses. 01 No. VSS (RY-YB-BR-OFF-RN-YN-BN)				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		01 No. ASS (4 position) 01 No. Digital Ampere Meter 01 No. Digital Volt Meter 03 No. 60/5A Current Transformers 03 Nos. R-Y-B Indication lamps 03 Nos. Cu Bus Bars complete with Nut & bolts, washers/insulation. 01 Nos. Earth Bus Bar 01 Nos. Neutral Bus Bar				
		OUTGOINGS	Job	1		
		05 Nos. 20 Amps SP MCB RC-6KA. 10 Nos. 16 Amps SP MCB RC-6KA.				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		DB-AC & POWER-GF				
		INCOMING (MAIN DB)				
		01 Nos. 100 Amps TP MCCB RC- 10KA 03 Nos. 2 Amps Protection fuses. 01 No. VSS (RY- YB-BR-OFF-RN- YN-BN) 01 No. ASS (4 position) 01 No. Digital Ampere Meter 01 No. Digital Volt Meter 03 No. 100/5A Current Transformers 03 Nos. R-Y-B Indication lamps				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		03 Nos. Cu Bus Bars complete with Nut & bolts, washers/insulation. 01 Nos. Earth Bus Bar 01 Nos. Neutral Bus Bar				
		OUTGOINGS	Job	1		
		11 Nos. 20 Amps SP MCB RC-6KA 19 Nos. 16 Amps SP MCB RC-6KA				
		DB-AC & POWER-ROOF TOP				
		INCOMING (MAIN DB)				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		<p>01 Nos. 60 Amps TP MCCB RC- 10KA 03 Nos. 2 Amps Protection fuses. 01 No. VSS (RY- YB-BR-OFF-RN- YN-BN) 01 No. ASS (4 position) 01 No. Digital Ampere Meter 01 No. Digital Volt Meter 03 No. 60/5A Current Transformers 03 Nos. R-Y-B Indication lamps 03 Nos. Cu Bus Bars complete with Nut & bolts, washers/ insulation. 01 Nos. Earth Bus Bar</p>				
--	--	--	--	--	--	--

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		01 Nos. Neutral Bus Bar				
		OUTGOINGS	Job	1		
		03 Nos. 25 Amps SP MCB RC-6KA. 04 Nos. 20 Amps SP MCB RC-6KA. 10 Nos. 16 Amps SP MCB RC-6KA.				
		DB-AC & POWER 1F				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		INCOMING (MAIN DB)				
		01 Nos. 100 Amps TP MCCB RC- 10KA 03 Nos. 2 Amps Protection fuses. 01 No. VSS (RY- YB-BR-OFF-RN- YN-BN) 01 No. ASS (4 position) 01 No. Digital Ampere Meter 01 No. Digital Voltmeter 03 No. 100/5A Current Transformers 01 No. 4 Pole Surge Protection Device 03 Nos. R-Y-B Indication lamps				

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		03 Nos. Cu Bus Bars complete with Nut & bolts, washers/ insulation. 01 Nos. Earth Bus Bar 01 Nos. Neutral Bus Bar				
		OUTGOINGS				
		10 Nos. 20 Amps SP MCB RC-6KA 20 Nos. 16 Amps SP MCB RC-6KA.	Job	1		
	WIRING IN CONCEALED CONDUITS					
		Supply, installation, and testing of Wiring of circuit from Distribution Board to Power socket for AC and heater ,	No	36		

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

		230 Volts, with Three nos. single core 6 sqmm PVC insulated 450/750 Volts grade stranded copper conductor cables in 1" dia Concealed/open PVC conduit laid underfloor / wall including PVC conduit, conduit accessories, etc. all accessories complete in all respects and as mentioned in Specification				
--	--	--	--	--	--	--

**ANNEX-C
PRICE PROPOSAL**

SOQ/ITB/2022/004

Name of Company: _____

Name of Bidder: _____

Company Stamp: _____

Signature: _____

Date: _____