

**ANNEX-C-PRICE PROPOSAL
LOT#2 MUHAMMAD KHAIL SCHOOLS**

A. REPAIR OF SCHOOL WORK SCHOOL# 13

S.NO	DESCRIPTION	NO	UNIT	QUANTITY	RATE	TOTAL
1	Scraping old Mud Plaster Works Scraping the old / existing & damaged mud Plaster completely , any thickness including the cost of CARRIAGE OF Surplus Materials Includes Loading, Unloading .as per instruction					
	Total		CFT	2180.00		
2	Providing and laying 2mm thick plastic and layer of Mud Plaster 2 to 2.5 inch on roof of all school rooms and hall of school and toilets adding straw etc. where required providing additional 5 feet T-iron as per instruction of engineer					
	Total covered area of roof		CFT	2500.00		
3	Construction of Veranda 100 feet x 10 feet, brick structure columns at 10 every foot spacing of 1.5 x1.5 ' heith 9' roof with main girder 10x 6 inch and brick tile-T-iron, and centre grider at every 10 feet to column 8x 6 inch with 2mm thick plastic and concrete layer of 2 inch. connection with exiting room properly as per instruction of engineer					
	Total		SFT	100.00		

	Providing and laying Mud Plaster On boundary wall, or Walls of rooms and hall of school including the cost of wood burada/straw					
	Mud Plaster					
	Total		SFT	8000.00		
	White washing three coats including dusting, filling the holes, cracks and removing inequalities using colour and Gelo mixing in it at if any, at any height. Including cost of door paint as oil paint for 10 doors, roof Grider ,T-rion etc complete in all respect.					
	Total		SFT	10000.00		
TOTAL- A. REPAIR OF SCHOOL WORK SCHOOL# 13						

B. REPAIR OF SCHOOL WORK SCHOOL# 36

S.NO	DESCRIPTION	NO	UNIT	QUANTITY	RATE	TOTAL
1	Scraping old Mud Plaster Works Scraping the old / existing & damaged mud Plaster completely , any thickness including the cost of CARRIAGE OF Surplus Materials Includes Loading, Unloading .as per instruction					
	Total		CFT	2500.00		
2	Providing and laying 2mm thick plastic and layer of Mud Plaster 2 to 2.5 inch on roof of all school rooms and hall of school and toilets adding straw etc. where required providing additional 5 feet T-iron as per instruction of engineer					
	Total covered area of roof		CFT	2500.00		
3	Construction of Verandah 100 feet x 10 feet, brick structure columns at 10 every foot spacing of 1.5 x1.5 ' heith 9' roof with main girder 10x 6 inch and brick tile-T-iron, and centre grider at every 10 feet to column 8x 6 inch with 2mm thick plastic and concrete layer of 2 inch. connection with exiting room properly and 1:2:4 concrete floor 6 inch as per instruction of engineer					
	Total	100.0	SFT	1000.00		

4	P.C.C Flooring : Providing & laying of 6 " P.C.C . 3" Flooring using crushed or broken stone graded 1:3:6, and 3 inch using 1:2:4 including curing, marble Patti at 3 feet square and boarder finishing compacting & finishing complete in all respect.					
	Total	1.0	CFT	500.00		10
5	Providing and laying Mud Plaster On boundary wall, or Walls of rooms and hall of school including the cost of wood burada/straw Mud Plaster NSR					
	Total		SFT	12000.00		
6	White washing three coats including dusting, filling the holes, cracks and removing inequalities using colour and Gelo mixing in it at if any, at any height. Including cost of door paint as oil paint for 22 doors, roof Grider ,T-rion etc complete in all respect.					
	Total		SFT	12000.00		
TOTAL B. REPAIR OF SCHOOL WORK SCHOOL# 36						
GRAND TOTAL(A+B)						

Name of Company: _____

Name of Bidder: _____

Company Stamp: _____

Signature: _____

Date: _____