

ANNEX-B3-LOT-3

CONSTRUCTION OF FLOOD PROTECTION WALL AT SURKHAB RV AREA DISTRICT PISHIN

S.NO.	DESCRIPTION	NO	L	B	D/H	QTY:
1	Excavation in foundation of buildings and bridges including layout, dressing, refilling around structures with excavated earth, watering & ramming lead upto 100 ft. (30m) & lift upto 5 ft. (1.5m). By Machinery. Shingle or Gravel. Protection Wall At Manda R/S & L/S	1	x 1148	x 4	x 4	= 18374 Cft
Total:-						= 18374 Cft
S-I-No.3-21 (B-iv)						
2	Filling and compacting soil, earth and boulders behind retaining walls (including excavation of soil and lead upto 50 ft. (15m) inclding transporation Sides and back tilling	100	x 100	x 5	x 8	400000
S-I-No. 3-30-1						Total:- = 400000 Cft
3	Providing and laying cement concrete using approved coarse sand and crushed aggregate 3/4" (19mm) & down gauge in foundation including					
Protection Wall 1st Bed		1	x 1148	x 4	x 0.5	= 2297 Cft

	S-I-No.5 - 8 (d)								
4	Providing, dressing and laying coursed rubble masonry in foundation, plinth and basement including scaffolding and curing. In Cement, Coarse								
	Protection Wall	2	x	1148	x	1	x	9	
									= 20670 Cft
									Total:- = 20670 Cft
	S-I-No.12 - 5 (b)								
5	Providing and laying plum concrete using approved								
4	coarse sand and crushed aggregate 1-1/2" (38 mm) & down gauge with 30% boulders including levelling,								
	Protection Wall 1st step	1	x	1148	x	4	x	4	= 18374 Cft
	Protection Wall 2nd step	1	x	1148	x	3	x	3	= 10335 Cft
	Protection Wall 3rd step	1	x	1148	x	2	x	2	= 4593 Cft
									Total:- = 33302 Cft

6	<p style="text-align: center;">S-I-No.5 - 47 (b)</p> <p>Providing and laying 1:2:4 cement concrete using approved coarse sand and crushed aggregate 3/4" (19mm) and down gauge in precast shelves coping, cornices, eave boards, hood, fencing posts and manhole covers etc. i/c formwork & its removal, compacting & curing in ground floor.</p> <p style="text-align: center;">Protection Wall</p>	<p style="text-align: center;">1 x 1148 x 2 x 1</p>	<p style="text-align: center;">= 2297</p>	<p style="text-align: center;">Cft</p>	
			Total:-	= 2297	Cft
7	<p style="text-align: center;">S-I-No.5 - 27 (a)</p> <p>Carriage of 100 Cft. (2.83 cu.m) of all materials like Clay, stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cft. (4.25 cu.m) of timber, by truck or by any other means owned by the contractor. 25 % Extra to be paid for hilly area, 25% Extra for Hard Area, 20% more for Kucha Road, 15% more for desert road.</p> <p>Lead Upto 22-30 Km with 25% extra for Hard Area</p>				
			Total:-	= 53972	Cft