## GENERAL REPAIR WORK FOR BLOCKS

#### LOT 6

#### PRICE PROPOSAL

# CIVIL WORKS

### DETAIL ABSTRACT SHEET

6.N 0	Description of Items	Quantity	Unit	Rate (Rs)	Amount (Rs)
	Sewerage Lin	e			
	Dismantling Rectangular compund 100 by 60 feet. Roof with Tile T-iron and mud layer and 1.5'walls with bricks with hieght of 18 feet and foundation of stone masonary complete in all respect. and handing over the material to owner and serplus material has to been disposed 5 KM away from center as per instruction.				
	away nom center as per instruction.	3000.00	cft		
	<b>Excavation in foundation</b> of buildings and bridges,including layout, dressing, refilling around structures with,excavated earth, watering & ramming lead upto 100 ft.,(30m) & lift upto 5 ft. (1.5m)				
		4500.00	Cft		
	<b>Providing and laying plain</b> hand mixed <b>1</b> : <b>4</b> : <b>8</b> cement concrete using sand approved source and crushed aggregate having maximum size upto 1 1/2" (38mm) & down gauge in foundation and plinth including leveling, compacting & curing.				
		375.00	Cft		
	Providing and laying 1:2:4 cement concrete using approved coarse sand and crushed aggregate PCC circular Pipes 18"dia as per instuction				
		500.00	RFT		
	Providing and fixing the steel 5mm thick mainhole 2'x2'fixed in concrete 2x'2' with main drain for sewerage line connecting to main line out side compund as per engineer instruction				
		500.00	Nos		
	Consturction of Main Septic tank with brick works wall and RCC covoers size (20'x 10'x 10')				
	Septic tank and connecting with sewarge line	1.00	Job		
	<b>Providing and laying plain</b> hand mixed <b>1</b> : <b>4</b> : <b>8</b> cement concrete using sand approved source and crushed aggregate having maximum size upto 1 1/2" (38mm) & down gauge in foundation and plinth including leveling, compacting & curing.				
	Flooring final	6600.00	Cft		
	Providing and laying 1:2:4 cement concrete using approved coarse sand and crushed aggregate 3/4" (19mm) & down gauge in foundation including leveling, compacting and curing.				
	out side flooring and path				
	Flooring /tuff tile	10000.00	Cft		
				Sub-Total	
		(	GRAND TO	TAL OF LOT-6	

Company Name:	
Name Of Bidder:	
Stamp & Sign:	
Date:	