

ANNEX-B

LOT-1 CONSTRUCTION OF UNHCR SAFE ROOM
BILL OF QUANTITIES

DETAIL ABSTRACT
SHEET

CIVIL WORKS

S.No	Description of Items	Quantity	Unit
CIVIL WORKS			
	Excavation in foundation of buildings and bridges, including layout, dressing, refilling around structures with excavated earth, watering & ramming lead upto 100 ft. (30m) & lift upto 5 ft. (1.5m)	14259.13	Cft
	Spraying anti-termite liquid Hepta color or equivalent mixed with water in the ratio of 1 liter : 40 liter.	2826.63	sft
	Providing and laying plain hand mixed 1 : 4 : 8 cement concrete using sand approved source and crushed aggregate having maximum size upto 1 1/2" (38mm) & down gauge in foundation and plinth including leveling, compacting & curing.	643.66	Cft
	Providing, fabricating and laying deformed Grade 60 steel reinforcement (deformed bar) for all kinds of R.C.C work in foundation, plinth and ground floor including the cost of straightening, removal of rust, cutting, bending, binding, wastage and providing such over-laps as are not shown on the drawings. The cost of binding wire and cement concrete spacer blocks or chairs for binding and holding the reinforcement in position is inclusive upto 15 ft. (5m) height		
	Footing, RCC walls and columns & foundation beam	10.10	
	Roof Beam	3.98	
	Slab	3.50	
	Total	17.575	ton
	Providing and laying 1:2:4 cement concrete using approved coarse sand and crushed aggregate 3/4" (19mm) and down gauge in sills and Bed Plate including formwork and its removal, compacting and curing	2501.63	Cft
	Providing asphalt membran sheet on vertical surface of R.C.C wall back side.	1360.00	sft
	Providing and laying first class solid burnt brick masonry (Brick Strength:1800psi-2000psi) including scaffolding, raking out joints and curing in ground floor superstructure and i/c cost of testing with 1:3	274.38	Cft
	Providing and laying 1 : 2 : 4 cement concrete using approved coarse sand and crushed aggregate 3/4" (19mm) & down gauge in foundation including leveling, compacting and curing.	258.75	Cft
	Providing and laying 1:2:4 cement concrete using approved coarse sand and crushed aggregate 3/4" (19mm.) and down gauge in plinth band, door band and roof band & Slab of required shape or section including formwork and its removal, compacting and curing in basement and ground floor but excluding the cost of reinforcement. slabs including formwork and its removal, compacting and curing Upto 6" (150 mm) thickness i) In basement, plinth and ground floor	994.88	Cft
	Cement plaster using Coarse Sand on soffits of ceiling, cantilever slabs, sides and soffits of beams, in basement and ground floor including making edges, corners and curing. 1/2 inch (13mm) thick cement sand plaster 1:4	1028.25	Sft
	3/4 inch (19mm) thick cement plaster using Coarse Sand on walls and columns in basement, plinth and ground floor including making edges, corners and curing. The mix ratio is 1:4 cement sand.	3679.50	Sft

**LOT-1 CONSTRUCTION OF UNHCR SAFE ROOM
BILL OF QUANTITIES**

**DETAIL ABSTRACT
SHEET**

CIVIL WORKS

S.No	Description of Items	Quantity	Unit
	Providing and laying super white 12"x12" marble tiles floor fine dressed on surface without winding in ground floor and laid over 1" (25mm) thick cement sand mortar 1:2 setting tiles with portland cement slurry over cement mortar, jointing and washing the tiles with white cement slurry including curing, rubbing and polishing including the cost of cement mortar. 1" (25 mm) thick marble tiles floor		
		1026.00	sft
	Providing and laying Conglomerate flooring (two coat work) having 1/2" (9mm) thick wearing surface comprising 1 part of cement & 2 parts of stone chips passing 3/16" sieve, over 1:3:6 concrete base using crushed aggregate laid in panels or approved pattern including formwork, curing, and surface finishing as approved by Engineer Incharge. mortar.		
		522.00	Cft
	Providing and laying 1/4" to 3/8" (6mm to 9mm) thick Glazed/ Matt tiles of any colour and size in ground floor laid over 1" (25mm) thick cement sand mortar base including jointing and washing the tiles with white cement slurry of matching color by using color pigment and curing		
		342.00	Sft
	Providing and laying (6mm to 9mm) thick Glazed,Non Glazed/ ceramic matt tiles of approved colour and size in laid over 1" (25mm) thick cement sand mortar base including jointing and washing the tiles with white cement slurry of matching colour by using colour pigment and curing		
		2126.00	Sft
	Providing and fixing aluminium / Metal ceiling with 2'x2' with required fitting of frame from ceiling to 6" and providing electrical points and 12 watt lights with required 4 gang switches board as per instruction of engineer .		
		916.00	Sft
	Providing and fixing moulded steel door frame of approved profile, manufactured from zinc-coated mild steel sheets 16 gauge made by Shahah Industries or equivalent standard conforming to B.S.S.1245, treated with special primer base paint all round, fitted with six fixing lugs, three steel hinges for fixing door shutters standard lock-strike plate, one sliding holt eye, and three rubber buffers, including cutting holes and making good damages to walls and filling the door frame cavity with lean cement mortar 1:4 as directed by the Engineer		
		52.00	Rft
	Providing and fixing 1.5" (38 mm) thick fully panelled First class deodar wood shutter fixed with ply/ hard board/ chip board/ Cement Fibre sheet and with approved nickle plated hinges and tower bolts		
		70.00	Sft
	Providing and fixing fully glazed single leaf hung/sliding aluminium windows, ventilators (Deluxe model - 1.6mm) of anodized champagne or approved color of Prime, Chawala, Pakistan Cable or any approved section as approved by Engineer incharge including aluminium fittings, 5 mm local tinted glass, lugs, cutting holes and making good the damages to walls.		
		86.00	Sft

**LOT-1 CONSTRUCTION OF UNHCR SAFE ROOM
BILL OF QUANTITIES**

**DETAIL ABSTRACT
SHEET**

CIVIL WORKS

S.No	Description of Items	Quantity	Unit
	Providing and fixing locks with brass or specially supplied screws including Door Closers and Floor Hinges of approved design including cutting wood to required shape	3.00	Each
	Distempering with Berger, ICI or equivalent synthetic polyvinyl emulsion finish of approved shade in two or more coats over and including the cost of priming coat including preparation of surface viz. dusting, sand papering or rubbing with pumice stone, filling cracks or holes, if any, removing blisters or other imperfections at any height and any floor. (@ atleast 2.20 Litre per 10 Sq.m)	1072.50	Sft
	Painting in ground floor or basement with Robbialac or equivalent super gloss synthetic enamel paint in two or more coats as per manufacturer's instruction on wood work over and including the cost of priming coat, surface preparation, rubbing down smooth, knotted, filling cracks, holes and joints.	70.00	Sft
Total			

**LOT-1 CONSTRUCTION OF UNHCR SAFE ROOM
BILL OF QUANTITIES**

**DETAIL ABSTRACT
SHEET**

CIVIL WORKS

S.No	Description of Items	Quantity	Unit
PLUMBING & SEWRAGE			
	Excavation in foundation of buildings and bridges,including layout, dressing, refilling around structures with,excavated earth, watering & ramming lead upto 100 ft.,(30m) & lift upto 5 ft. (1.5m)	697	Cft
	Providing and fixing white glazed vitreous China Porta squatting type W.C. pan with integral treads similar to Orissa type.	1.00	Each
	Providing and fixing white glazed vitreous China Porta squatting type english Commode with integral treads similar to Orissa type.	1.00	Each
	Providing and fixing ICL /Karam cera or approved equivalent make glazed earthen ware shower tray including fittings, bib cok, stop cock, shower kit, trap and making requisite numbers of holes and making good with approved material	2.00	Each
	Providing and Installing uPVC pipe IIL, Dadex or equivalent make registered with PSQCA in tubewell bore hole and/or laying, cutting, jointing and testing uPVC pipe lines in trenches. Class B 3" (75 mm) inner dia.	174.25	P.Rft
	Providing and Installing uPVC pipe IIL, Dadex or equivalent make registered with PSQCA in tubewell bore hole and/or laying, cutting, jointing and testing uPVC pipe lines in trenches. Class B 4" (100 mm) inner dia.	348.50	P.Rft
	Providing and fixing brass bib cock/ stop cock of approved make	4.00	Each
	Providing and fixing export quality glazed earthen ware wash basin manufactured by ICL Boch/Karam Cera or equivalent approved make with single hole chromium plated mixer tap 1/2" (15mm), pillar tap delux, stop cocks, C.I. or W.I. brackets 6" (150mm) built into walls 1.5" (40mm) C.P. brass waste with malleable iron or C.P. brass trap with malleable iron or brass union and making requisite number of holes in walls, plinth and floor for pipe connections and making good with approved material Extra over above for providing and fixing white glazed earthen ware pedestal manufactured by ICL/Karam Cera or approved equivalent make.	1.00	Each
	Providing and fixing approved quality C.P. brass toilet paper holder Master /Sonex or equivalent make	1.00	Each
	Providing and fixing looking mirror of Belgium/ Malaysian/ Indonesian glass with chromium plated screws	1.00	Sft
	Providing and fixing approved quality chromium plated towel rail with bracket and screws	1.00	Each
	Supply and install 35 gallons electric geyser	1.00	Each
	Total		

**LOT-1 CONSTRUCTION OF UNHCR SAFE ROOM
BILL OF QUANTITIES**

**DETAIL ABSTRACT
SHEET**

CIVIL WORKS

S.No	Description of Items	Quantity	Unit
Electrical works of Building			
	Light circuit concealed wiring with length upto 75 ft. (25m) 7/29 main and 3/29 for lights and switches from the distribution board to point/switch with 3x2.5 Sq.mm PVC insulated single core copper conductor Pakistan Cables, Pioneer, Newage or approved equivalent cables for offices/multi storeyed buildings.	15.00	P/Point
	Wiring of 5 Amps. socket outlet with 4 sq.mm PVC insulated single core copper conductor cable including 3/4" (20mm) dia. PVC conduit, 8.7sq.mm (10SWG) copper wire as earth continuity conductor and wiring accessories such as bends, elbows, junction boxes etc	12.00	P/Point
	Same as item no 31.3 but wiring for 5Amp . socket outlets from nearest available circuit with a lenth upto 6m (19.68 ft).	12.00	P/Point
	Supply and install 1-gang, 5 Amp, 250 Volt,. plate type moulded Clipsal/Schneider or equivalent imported switch including appropriate size plastic box to be fixed recessed in wall. Description same as in Item 30-129 but with 4 up to 6 gang switch.	4.00	No
	Supply and installation of 5 Amp. 250 Volt, moulded, two-way single pole, flush mounting type light control single switch including appropriate size plastic box to be fixed recessed in wall.	5.00	No
	Supply and install combined 2/3 pin 5 Amps, 250 Volt switch socket unit including plastic box to be fixed recessed in wall. supply and instalation of 3 pin 15 Amp switch socket unit	8.00	NO

**LOT-1 CONSTRUCTION OF UNHCR SAFE ROOM
BILL OF QUANTITIES**

**DETAIL ABSTRACT
SHEET**

CIVIL WORKS

S.No	Description of Items	Quantity	Unit
	Supply and install Energy Saver electric bulbs 25W Philips energy saver	15.00	Each
	Supply and install 10" (250 mm) sweep exhaust fan including plastic louvers.	1.00	Each
	Supply and install 56" (1.42 m) sweep ceiling fan with fan hook and dimmer complete with all accessories.	6.00	Each
	Supply and provision of NASGAS Water cooler 35 Gallon with water filter best quality Aqua/equivalent with warranty including electrical and plumbing fittings.	1.00	Each
	Supply and provision of Dawlance Water Dispenser WD 1060 including electrical fitting	1.00	Each
	Allow for a complete ICT installations - including concealed wiring from point to point with length upto 10 ft. (3m) with 3x1.5 Sq.mm PVC insulated single core copper conductor Pakistan Cables, Pioneer, Newage or approved equivalent cables. I/C Concealed wiring with 3/4" (20 mm) dia. PVC conduit and accessories such as bends, elbows, junction boxes etc. according to drawings	1.00	job
	Supply and install electric Split Air Conditioner "Gree" 1.5 Ton with rated heating and cooling capacity of 18000 (5400 - 19800) BTU including the wiring required for 7/29 point and switch	1.00	
	Provide, install, test and commission recessed wall mounting type distribution board fabricated from 16 SWG steel sheet, powder coated with approved color back box comprising one incoming MCCBTP/ 60A and outgoing 9 single phase MCB of various capacity having overload & short circuit protection and of 6 KA braking capacity complete with internal wiring earthing, neutral link, termination blocks, phase indicating lights alongwith 500V voltmeter.	1.00	P.Job
Total			