

ANNEX-B5

LOT 6 GENERAL REPAIR WORK FOR BLOCKS

BILL OF QUANTITIES

CIVIL WORKS

DETAIL ABSTRACT SHEET

S.No	Description of Items	Quantity	Unit
Sewerage Line			
	Dismantling Rectangular compound 100 by 60 feet. Roof with Tile T-iron and mud layer and 1.5'walls with bricks with height of 18 feet and foundation of stone masonry complete in all respect. and handing over the material to owner and surplus material has to be disposed 5 KM away from center as per instruction.		
		3000.00	cft
	Excavation in foundation of buildings and bridges,including layout, dressing, refilling around structures with,excavated earth, watering & ramming lead upto 100 ft.,(30m) & lift upto 5 ft. (1.5m)		
		4500.00	Cft
	Providing and laying plain hand mixed 1 : 4 : 8 cement concrete using sand approved source and crushed aggregate having maximum size upto 1 1/2" (38mm) & down gauge in foundation and plinth including leveling, compacting & curing.		
		375.00	Cft
	Providing and laying 1 : 2 : 4 cement concrete using approved coarse sand and crushed aggregate PCC circular Pipes 18" dia as per instruction		
		500.00	RFT

LOT 6 GENERAL REPAIR WORK FOR BLOCKS**BILL OF QUANTITIES****CIVIL WORKS**

DETAIL ABSTRACT SHEET

S.No	Description of Items	Quantity	Unit
	Providing and fixing the steel 5mm thick mainhole 2'x2'fixed in concrete 2x2' with main drain for sewerage line connecting to main line out side compund as per engineer instruction		
		500.00	Nos
	Consturction of Main Septic tank with brick works wall and RCC covoers size (20'x 10'x 10')		
	Septic tank and connecting with sewerage line	1.00	Job
	Providing and laying plain hand mixed 1 : 4 : 8 cement concrete using sand approved source and crushed aggregate having maximum size upto 1 1/2" (38mm) & down gauge in foundation and plinth including leveling, compacting & curing.		
	Flooring final	6600.00	Cft
	Providing and laying 1 : 2 : 4 cement concrete using approved coarse sand and crushed aggregate 3/4" (19mm) & down gauge in foundation including leveling, compacting and curing.		
	out side flooring and path		
	Flooring /tuff tile	10000.00	Cft
			Total
			G.Total