

ANNEX C: FINANCIAL OFFER FORM**RFQ NO.2024/SOP/SCU/009****UNHCR SUB OFFICE PESHAWAR****RENOVATION WORKS AT VRC AZAKHEL NOWSHERA****BILL OF QUANTITIES**

S.No.	ACTIVITIES DESCRIPTION	Qty	Unit	Unit Rate (PKR.)	Total Amount (PKR.)
1	Metallic paint works of existing benches in the facility, of approved color	230	No.		-
2	Repair of existing benches including repair/replacement of wooden planks and nails etc.	70	No.		-
3	Painting Distemper (2 coat) of family segregation hall, 2 halls, of approved color	4600	sqft		-
4	Painting of main entrance gates, both sides of VRC and PCM, of approved color	960	sqft		-
5	Paint works of external red brick wall	1500	sqft		-
6	Paint works of external shed pillars and frame in white color	1100	sqft		-
7	Paint works of BHU containers no. 19,20, 26, of approved color	1350	sqft		-
8	Paint works of containers no. 1,4,17,26, of approved color	1800	sqft		-
9	Painting of refugees' entry gate and fence	950	sqft		-
10	Paint works of 3 backup generators	960	sqft		-
11	Plain Cement Concrete (3") flooring in refugee screening area, 1;2:4, with proper compaction	950	cuft.		-
12	Extension of screening shed, including additional pillars and other fixtures	510	sqft		-
13	Painting of shed frame of screening area including the extension area (item. 11) in white color	4300	sqft		-
14	Cleaning, Dressing, Leveling & Compaction of existing surface, 3" thick PCC (1:4:8) & 2" thick Tuff Tiles installation in red and yellow color, over 2" thick sand, Complete in all respects	3550	sqft		-
15	Repair of entrance gate between PCM and VRC	1	Job		-
16	Painting of sign boards-Main GT road, VRC entrance and inside VRC	1	Job		-
17	Repair of female and male search cabins, (7'x7'x8') each	2	No.		-
TOTAL AMOUNT in PKR.					-

Company Name:

Contact Details:

Signature / Stamp:

Note: Vendors must submit both Excel & Pdf formats of Financial Offers.